



Proposal for Services

Parking Lot Repaving and Resurfacing Proposal

Must be received by 10:00 AM on September 24th, 2018

1. Services to be performed at Shiloh Tower 1525 27th Street Zion, Illinois

Excavate, grinding and installation of new asphalt to newly developed area. Excavate the existing parking lot area, including the new portion. A proposed schedule must be submitted with the bids detailing the approximate days and plan orders and all scheduling must be pre-approved with LCHA project staff and management. The parking lot area must be safe and accessible at all times.

Note: Please contact Kent Britton kbritton@lakecountyha.org or 847-417-4034 to schedule a site visit before submitting a proposal. **Site tour is mandatory, which will be held on Monday, September 17th at 10:00 AM.**

JULIE has a mark in the unimproved area that needs paving.

The statement of work:

- Excavate the entire lot and install new asphalt in improved and unimproved areas using the standards listed below
 - Surface is to be smooth and level after asphalt is installed
 - All lots are to be restriped to match existing for placement and handicap striping for local code meeting the latest version of Illinois Department of Transportation's Standard Specifications for road and Bridges Construction
 - 78001100 Paint Pavement Marking – Line 4"
 - 78001130 Paint Pavement Marking – Line 6"
 - 78001180 Paint Pavement Marking – Line 24"
- Storm water caps, drains, grates, collars and piping to be repaired or replaced as needed to proper operation, contractor to work with the local Public Works Department

Excavating, grading and backfilling the improved/unimproved area with laying new bedding materials, asphalt and all associated materials to match pad size of total area, pitched away for drainage at a minimum of 1" per 10'. Replace to height of existing and/or required by requirement/code

- Furnish gravel to regrade and compact using a at a minimum 6/4 table
- Pave at least one binding layer and one asphalt layer of no less than 1.5 inches each, compacting approximately
- 6" of compacted and leveled stone bedding
- Grade asphalt toward drains as appropriate, keeping drains free of debris
- 4" of compressed and leveled N50 mix "C" hot asphalt. Layer in a 2 stage process of 2" of binder course and 2" of surface asphalt
- Edges to be tamped on an upward angle

Disposal of all scrap and removed material and site cleanup to include sweeping lot for debris

Re-Stripe and remark parking lot maximizing number of handicapped and non-handicapped spaces. Handicapped spaces to follow State of Illinois guidelines. Contractor to work with LCHA for hash mark striping any non-parking or maintenance drive areas

Secure and supply cost of any needed permits including but not limited to Construction, if required by The City of Zion. Must be secured by contractor prior to commencing any on site work, displayed on site as appropriate and signed copies must be turned in to LCHA prior to final payouts. Approvals/Final inspections per City of Zion.

Total \$ _____

10% Contingency _____

Total with Contingency _____

Note: Should you elect not to include a contingency amount, be advised that any additional statement of work or scope of services will be the responsibility of the contractor and not LCHA

Contractor _____

Address _____

Email _____

Phone _____

2. Primary Contacts/Notice Addresses

Lake County Housing Authority
Kent Britton
33928 N. US Highway 45
Grayslake, Illinois 60030
Phone: 847-223-1170 x 2660

3. Terms

5 calendar days to complete the project from approved plans.

All work to be done up to code

- Pursuant to Section 15 of the Substance Abuse Prevention on Public Works Projects Act, 820 ILCS 265/1 *et seq.*, a copy of the Contractor's written substance abuse prevention program must be submitted prior to the commencement of *the Work*
 - If subcontractors are to be used they must be listed on the bid form. The general contractor or prime contractor must complete at least 12% of the project by himself or his employees. The job may not be subcontracted more than 88%. If subcontractors are used each subcontractor must submit proof to demonstrate the subcontract relationship (contract, incorporation papers, etc) and a Certificate of Insurance covering general liability and workers compensation for the subcontractor and employees
 - a. The subcontractor shall follow the same wage requirements as above for employees
 - b. If subcontractors hire other subcontractors, all requirements apply
- All work to be done in a workmanlike manner
\$100 daily fines for late work start dates or contract surpassing timeframe

4. Key Contact

Please contact Kent Britton

Total Cost should include the prevailing wage for labor and Davis Bacon